
REDLINEMD

WEBSITE REDESIGN · DESIGN RATIONALE

Don’t sign your first contract blind.

How the Redline MD site was redesigned to convert Google Ads traffic on mobile and desktop, and to earn the trust a physician needs before handing over a high-stakes contract.



Live site
redline-md-alpha.vercel.app

Repository
github.com/FelipeGaigher/Redesign-RedlineMD-

Design
Felipe Gaigher, for the Foundey design challenge

01 · DIAGNOSIS

Why the current site loses doctors

35% of traffic arrives on mobile, but over 90% of revenue comes from desktop. Clicking through the current site on a phone explains most of it.

The funnel ends in a Google Form. Every “Get your Analysis” button opens `forms.gle`, and a form with a file upload asks the visitor to sign in to Google. A doctor who just tapped an ad, often without the PDF on that phone, stops right there. The sample report is a Google Drive file.

What erodes trust on the current page

Issue	Why it matters to a physician
Logo reads “Medical Contract Reiew”	A typo on a product that promises to catch errors in your contract.
Hero mockup shows “License Grant”, “ACME Corp”	A generic commercial-contract dashboard. Nothing about tail coverage, non-competes or compensation.
“Without” screenshot has garbled text	Looks AI-generated, which is the exact doubt a buyer of AI legal review already has.
Numbers disagree ($10,000 vs $50,000, “30% salary”)	Unsourced, inconsistent claims read as marketing, not evidence.
Five certification badges with no links; empty footer	No privacy policy, terms or contact on a site that claims GDPR and SOC 2.
No price explanation, no “how it works”, no FAQ	The questions a cautious buyer has go unanswered.

Goal 1 · Convert ad traffic

One clear action, frictionless upload on any device, and a path for the visitor who can’t upload right now.

Goal 2 · Earn trust

Show the real product, keep numbers honest, answer “is this legal advice?”, and look like law and medicine, not a generic AI startup.

02 · PRODUCT VISION

Who we are selling to, and what they fear

The user

A resident or fellow, 28 to 35, finishing training and signing a **first attending contract**. Carries $200k+ in student debt. Expert in medicine, new to contracts and negotiation. Researches on the phone between shifts; signs on the laptop.

Arrives from Google Ads searching “physician contract review” or “tail insurance”: intent is already high. The page has to confirm, reassure and get out of the way.

Job to be done

“Before I sign, I want to know what in this contract could cost me money, and what I can ask for, without paying $1,000+ or waiting a week for a lawyer.”

Objections the page answers, in order

Doubt	Answer on the page
“Can I trust an AI with this?”	The hero shows a real clause being redlined; built with input from physicians and healthcare attorneys; FAQ states plainly it is not legal advice.
“Who sees my contract?”	AES-256 encryption, SOC 2 Type I, ISO 27001, GDPR; deleted after review; never shared with the employer.
“Is $199 worth it?”	$199 flat vs $500+ for an attorney, against $10,000+ of tail-coverage exposure.
“How fast?”	A free risk preview in under a minute; the full review within 24 hours.
“What if it doesn’t help?”	Money-back guarantee (to confirm with the client).

03 · THE OFFER

What $199 includes, and why it beats an attorney

$199

Flat price. No hourly billing, no calls to schedule.

24h

Full redlined review delivered within 24 hours. Risk preview in under a minute.

$10,000+

Typical tail-coverage exposure a single missed clause can cost when leaving a first job.

Included in the $199

- **Redlined copy** of the contract with suggested language for every flagged clause.
- **Full financial analysis**: a dollar estimate for each risk (tail coverage, non-compete buyout, below-median base pay) and the total exposure if signed as-is.
- **Negotiation script** ready to send to the recruiter, citing the clause numbers.
- **Up to 3 contracts, up to 30 pages each** (the current site's "three reviews for the price of one"), useful when comparing offers.
- **Free risk preview** before paying: the first risk is shown immediately; the rest unlock with the full review.

Redline MD vs an attorney review

	Redline MD	Traditional attorney review
Price	**$199 flat**	$500+, often billed by the hour
Time to result	**Preview in under a minute, full review in 24h**	Days to a week, after scheduling
What you get	Redline, financial analysis in dollars, negotiation script	Comments and a call
Specialty context	Terms compared with what doctors in your specialty get	Depends on the attorney
Needs a lawyer later?	The review becomes the brief, so fewer billable hours	—

The comparison is deliberately **not** at the top of the page. The page sells the product first (hero, how it works, what we check); the price argument lives in the hero price card, the numbers strip and the FAQ.

04 · USER FLOW

From the ad to the negotiation email

1
Ad click
Lands on the hero: the headline names the audience and the stakes.

2
Sees the product
The redline animation shows what the review does in 3 seconds.

3
Upload your contract
One yellow button, always reachable (sticky bar on mobile).


4
Upload sheet
Drag and drop on desktop; file or camera on mobile.

4b
No file on the phone?
“Email me a secure upload link”: the intent is kept, finished on the laptop.


5
Analysis
Visible checklist: reading, tail coverage, non-compete, termination.

6
Free preview
“3 risks found”: one shown with its dollar exposure, two locked.


7
$199 → 24h
Redline, financial analysis and script; the doctor negotiates.




Upload sheet, idle: drag and drop, formats, the email-link path, security line.



Analyzing: the checklist shows work happening, which builds trust in the result.



Uploading: encrypted progress for the named file.



Result: 3 risks, one visible with ~$12,000 exposure, CTA “Get full review for $199”.


Everything is simulated in the browser for this concept; no file leaves the device. In production the sheet would host the checkout (Stripe) instead of the Google Form.

05 · PAGE WALKTHROUGH

Section by section


The two sections built to full finish are **the hero with the upload flow** and **How it works**. The rest is assembled from the same tokens and components to give them context.

Hero




Two-tone headline (charcoal + brand red on "blind."), one yellow CTA, the sample report link, three assurances. On the right, real footage of a physician with the product working over it: § 7.3 tail coverage struck in red, employer-paid language inserted in green, a risk comment with the dollar exposure. A price card floats in the corner: $199 flat vs $500+, up to 3 contracts.


Who it's for, and the numbers




A slow marquee of specialties replaces a client-logo wall (no permission to use institutions' logos). The numbers sit as a quiet strip right under the hero, not a section of their own: $199, 24h, 3,000+ contracts reviewed (the client's claim), $10,000+ exposure.

How it works (desktop): pinned scroll









The left column stays pinned while three tall panels scroll on the right. The step whose card crosses the middle of the screen takes over the text, and progress dashes show where you are. Each panel assembles back card first, then front card, then rows one by one: (1) uploading from the phone, (2) the redline with a risk summary, (3) the recruiter email with the full financial analysis behind it.


What we check



Inputs → engine → findings. The contract, specialty benchmarks and state law flow into the Redline MD engine (live clause counter); findings land one by one with a Risk or Review tag, and a skeleton keeps “analyzing”.


Humanizing bands






Full-bleed video with one statement each. “Your first attending offer arrives in the middle of residency” names the real moment; “Read it before you sign it.” closes with the CTA over a signature in close-up.

Proof and security




Dark section with three plain promises instead of unlinked badges, and testimonials labeled “Illustrative” so nothing reads as fake social proof.

FAQ and footer




Four questions doctors actually ask, starting with “Is this legal advice?”. The footer carries the disclaimer, links and the design-concept credit.


Mobile first




Hero at 390px: headline, CTA full width within thumb reach.



Sticky bar appears once the hero CTA scrolls away: price + “Upload contract”.



Upload as a bottom sheet: file picker or camera.



No file on the phone: the secure link is emailed; the doctor finishes on the laptop.

On mobile, How it works becomes an auto-advancing accordion with the live preview below it; the pinned-scroll version is desktop only, as in the reference.

06 · HUMANIZING THE PAGE

Removing the “AI template” look

AI-generated pages share the same tells. Each one was replaced by a decision that comes from the subject: law, medicine, a contract.

Generic AI tell	What the redesign does instead
Abstract dashboard mockup	A real physician clause (§ 7.3 tail coverage) redlined like Word track changes.
Stock smiles, gradient blobs, sparkles	Footage of residents, a clipboard, a signature: the people and the moment the product is about. No decorative gradients; the only gradient is the scrim that keeps text legible over video.
Icon in a tinted box, grid of identical cards	Icons sit bare at text size; facts are ruled lists; cards only for real units (a finding, a quote, a file).
Inflated copy (“revolutionary”, “seamless”)	Facts: $199, 24 hours, up to 30 pages, § 7.3, ~$12,000.
Unlinked badges and invented numbers	Plain security promises; client claims kept as stated; examples and proposals labeled as such.
Purple startup palette, default fonts	The client’s own red, navy and yellow; one grotesk family; mono only for clause numbers and file names.

> Checked with the **sem-plastico** detector (a lint for AI-template patterns) on every component: zero findings.

Video sources

Three clips from Mixkit (free commercial license, no attribution required), compressed to 270–750 KB each, with a poster frame. They download only when they approach the viewport and pause off-screen.

07 · MOTION AND INTERACTION

Movement that explains, never decorates

Pattern	Spec	Purpose
Smooth scroll	Lenis, duration 1.1s, ease-out quart	Calm, premium reading pace; anchor links glide to sections.
Headline reveal	Each line rises from a mask, 700ms, 120ms apart; red rule draws in	Puts the eye on the promise first.
Section reveal	Fade + 24px rise, 500ms, 80ms stagger	Reveals hierarchy in reading order.
Redline loop	6s cycle: strike → insert → risk comment; paused off-screen	The product explained in 3 seconds; the only continuous motion near the CTA.
Counters	0 → value in 1.2s, once	Numbers feel earned, not pasted.
Pinned scroll (How it works)	Text swap 350ms; back card 600ms, front +350ms, rows 350ms apart	Tells the 3 steps at the reader's own pace.
Accordion autoplay (mobile)	6.5s per step, progress rule fills	Same story in a phone-sized format.
Checks diagram	Flowing connectors, live counter, findings 1.1s apart	Shows the engine working.
Buttons	Hover darkens; arrow slides 4px	Clear affordance without noise.
Nav	Transparent at top; white + blur after 40px	Content first, navigation when needed.
Upload sheet	Slides up 350ms; drag state scales 1% with red dashed border	Immediate feedback on drop.

Accessibility: `prefers-reduced-motion` turns off smooth scroll, loops, counters, marquee and video (posters only), and shows every element in its final state. Focus is visible, touch targets are 44px or larger, and text contrast meets WCAG AA.

08 · BRAND AND DESIGN SYSTEM

The client’s brand, made to look trustworthy

Logo, red, navy and yellow are kept from the current site (the misspelled tagline is cropped). Green is the only addition: a redline needs a color for accepted language. Every value is a token; components use no raw hex.



Red
#D21A17 · bolt, “blind.”, struck text, risk



Navy
#0E2E54 · headings, dark sections

Yellow
#FFD55A · primary CTA only



Ink
#222222 · body text



Muted
#4E4E4E · secondary text

Wash
#F6F5F4 · alternate sections



Accept
#1F7A4D · inserted language

Foundation	Decision
Type	Hanken Grotesk (variable, self-hosted): display 40→68px / 600, section titles 30→40px, body 16–19px. IBM Plex Mono only for clause numbers, file names and counters. No serif.
Two-tone titles	Base line in ink, the stakes in the brand red. One emphasis per title, never italic.
Radius	14px for cards, panels, buttons and video; 8px for tags.
Depth	Two shadow steps: floating elements and the upload dialog.
Spacing	4px scale; sections 64px mobile / 96px desktop; 1240px container.
Buttons	One primary per screen (yellow, charcoal text, 13:1 contrast); secondary is navy outline; tertiary is a text link.
Languages	English and Portuguese, switch in the nav; starts in the device language.

Full token and component list: `DESIGN-SYSTEM.md` in the repository.

09 · SOURCES AND NEXT STEPS

What comes from the client, and what is a proposal

From the current site

- $199 flat, results within 24 hours, up to 30 pages
- 3,000+ contracts reviewed
- “Three contract reviews for the price of one”
- Full financial analysis
- AES-256, SOC 2 Type I, ISO 27001, GDPR
- The sample report PDF (linked from the hero)

From the brief

- $500+ attorney comparison; $10,000+ tail exposure (the site says “up to $10,000”)

Proposals to confirm

- Money-back guarantee
- Deleted after review; never shared with the employer
- Free risk preview before paying
- “Email me a secure upload link”
- Comparison against specialty and state benchmarks
- Testimonials (labeled illustrative)
- Dollar figures inside mockups are examples

With more time

- A/B test the headline on paid traffic only (“blind” vs a tail-insurance-led line).
- One landing page per Google Ads keyword cluster (tail insurance, non-compete, residency to attending), reusing these components.
- Real social proof: named reviews, advisors with credentials, the review count with a date.
- Native checkout inside the upload sheet, and the email-link flow wired to a backend.
- Lighthouse pass on mobile: lazy-load the motion library, measure and trim.

Speed vs quality

The first part of the time went to diagnosis, because the biggest problem was the funnel, not the layout. Then two sections were finished completely, with every state, both breakpoints and reduced motion, instead of many sections at average quality. Everything else reuses the same tokens and components, so extending the page is assembly, not new design.

Design concept by Felipe Gaigher for the Foundey design challenge. Redline MD name, logo and claims belong to their owner and are used here only for the exercise.